



**NATIONAL INSTITUTE FOR EMPOWERMENT OF PERSONS WITH MULTIPLE DISABILITIES (NIEPMD)**

(Department of Disability Affairs, Ministry of Social Justice & Empowerment, Govt. of India)  
E.C.R.Muttukadu Kovalam P.O, Chennai- 603 112

NIEPMD/Estate 6(29)/2013-14

08/05/2014

To,

Reputed Agencies

**Sub:** Calling Quotation for the proposed Hearing Aid room wooden partition works ...reg

Sir,

The National Institute for Empowerment of Persons with Multiple Disabilities (NIEPMD) is established by the Ministry of Social Justice and Empowerment, Govt. of India is functioning at Muttukadu, Chennai – 112. NIEPMD invites tender for the wooden partition works.

S.No	Description	Area(Sq.ft) Approximately	Rate	Amount
1.	Wooden partition works up to the ceiling height using 75mmX75mm teak wood second class frame and the grid made by as per the drawing enclosed and covered with the 6mm plywood duly pasted with the 1mm thick laminate and both side	<b>100sqft</b>		
2.	Providing and fixing ISI marked flush door , shutter, core of block board construction with frame of first class hard wood and well matched teak 3ply veneering with vertical place are cross bands and face veneering an both faces of shutters, shutter including 12mm minimum depth an all edges of shutter including stainless steel butt hinges with necessary stainless steel /cp brass screw	<b>20sqft</b>		
3.	Wardrobe/continuous table arrangement to accommodate minimum 5 persons with two draws and one openable cabinet duly finished with external laminate and internal painting and necessary accessories and like locks handle brass lights and etc. (size -22'X2'X2.5')	<b>22Rft</b>		
4.	Carpet flooring including the fixing the finished floor with all necessary arrangements	<b>200sqft</b>		
5.	Supply , installation of Spilt type AC units of nominal cooling capacity 4500 kcal/Hr (1.5TR) , 5 star rating (suitable for operation on single phase 230 volts , 15Hz , Ac supply ) along with 4KVA voltage stabilizer LV/HV cut off , built in time lag , auto restart facilities on restoration of power and suitable for input voltage range of 170-270 volts and output 220+/- 10% etc. complete as required at site	<b>02Units</b>		

	(make :VOLTAS )			
6.	Supply, installation , testing and commissioning additional inter connecting copper control cables and refrigerant pipe lines etc. as required	<b>10mtr</b>		
7.	Supply, installation , testing and commissioning of cable management system for protection copper control cables and refrigerant pipe lines etc. as required	<b>20mtr</b>		
8.	Supply, installation , testing and commissioning of additional length of drain pipe (20mm PVC) etc are required	<b>20mtr</b>		
9.	Providing and fixing additional power outlets with wiring and MCB DB:s/MCB:s	<b>02 locations</b>		
Total amount				

The quotation clearly mentioning top of envelop as **“for the proposed Hearing Aid room wooden partition works ”** should reach on or before **30<sup>th</sup> May 2014** NIEPMD by speed post/courier /person –drop the quotation in to the Tender box which is kept in the Main building (3<sup>rd</sup> floor )

Yours faithfully,  
Sd/-  
(S.SANKARA NARAYANAN)  
Deputy Registrar (Admin)