
## National Institute for Empowerment of Persons with Multiple Disabilities (NIEPMD)





NIEPMD/Estate 6(24)/2013-14 To,

15/09/2014

(List of Agencies / Contractors)

<u>Sub:</u> Calling Quotation for Petty Civil works in the Library Section –provision of false ceiling...reg.

Sir,

The National Institute for Empowerment of Persons with Multiple Disabilities (NIEPMD) is established by the Ministry of Social Justice and Empowerment, Govt. of India is functioning at Muttukadu, Chennai – 112. NIEPMD invites tender for Petty Civil works in the Library Section –provision of false ceiling other works.

S.No	Description	Area( $ extbf{M}^2$ ) Approximately	Rate	Amount
	Detail Enclosed 01 Pages			

The quotation clearly mentioning top of envelop as "for Petty Civil works in the Library Section –provision of false ceiling other works" should reach on or before 30<sup>th</sup> September 2014 NIEPMD by speed post/courier /person –drop the quotation in to the Tender box which is kept in the Main building (3<sup>rd</sup> floor)

Yours faithfully,

(S.SANKARA NARAYANAN)
Deputy Registrar (Admin)

S.No	Description	Quantity	Rate	Amount
1.	Providing and fixing 15mm thick USG radar mineral fibre false ceiling tiles or equivalent of size 600X600mm in true horizontal level suspended on interlocking metal grid of hot dipped galvanized steel section(galvanized @170GSM/sqm) consisting of main 'T' runner suitably spaced at joints to get required length and size 24X38mm made from 0.3mm thick(minimum) sheet spaced@ 1200mm Centre to Centre and cross 'T' of size 24X25 mm made of 0.3 mm thick (minimum)carried over:  Sheet 1200mm length spaced between main 'T' @ 600mm Centre to Centre to form a grid of 1200X600 mm and secondary cross 'T' of length 600mm and size 24X25 mm made from 0.3 mm thick (minimum)sheet to be interlocked at middle of the 1200X600mm panel to form grid of 600X600mm and laying 15mm thick mineral fibre false ceiling tiles of approved texture in the grid including wherever required cutting /making opening for services like diffusers, grills, light fittings, textures, smoke detectors etc.  (1).Suspended from ceiling using G.I slotted cleats fixed to ceiling with 6mm dia. And 50mm long dash fasteners, 4mm G.I adjustable rods with galvanized level clips spaced @ 1200mm Centre to Centre along main 'T' bottom exposed width of 24mm of all 'T' shall be painted with poliyester paint at all heights as per specifications, drawings and as directed by the Engineer-incharge  Ceiling area will be measured for the purpose of payment.  (2)the mineral fibre ceiling shall be either precast (moulded)or wetted product and shall have NRC value of 0.50(minimum)CAL 35-39, light reflection 84% (minimum), fire rating class 'A' and also having thermal resistance "(R)"=0.33 sqm-deg C/W	200M²		
2.	Supply and fixing the false ceiling lights – model no: FBS 450/236W D6(PW)(AG)with lamp-PLL-36/86 4P	15 No's		
3.	(a).Supply , installation of Spilt type AC units of nominal cooling capacity 4500 kcal/Hr (2.0TR) , 5 star rating (suitable for operation on single phase 230 volts , 15Hz , Ac supply ) along with 4KVA voltage stabilizer LV/Hv cut off , built in time lag , auto restart facilities on restoration of power and suitable for input voltage range of 170-270 volts and output 220+/- 10% etc. complete as required at site (make :VOLTAS )  (b).Supply, installation , testing and commissioning additional inter connecting copper control cables and refrigerant pipe lines etc. as required (c).Supply, installation , testing and commissioning of cable management	04 No's 20M		
	system for protection copper control cables and refrigerant pipe lines etc. as required  (d).Supply, installation , testing and commissioning of additional length of	20M		
	drain pipe (20mm PVC) etc are required	20M		
4.	Wall/ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade.	150M <sup>2</sup>		